FAYETTE COUNTY ZONING DEPARTMENT

140 Stonewall Avenue West, Suite 202-A Fayetteville, Georgia 30214 (770)460-5730, ext. 5419

Aaron Wheeler, Zoning Administrator Robyn Wilson, Zoning Coordinator Delores Harrison, Zoning Technician (770)460-5730, ext.5161 (770)460-5730, ext.5162 (770)460-5730, ext. 5394 Fax Number: (770)460-8663 Zoning@admin.co.fayette.ga.us

APPLICATION TO THE ZONING BOARD OF APPEALS

(at Zoning Department, Suite 202-A)

COPIES OF ORDINANCES

David Bartosh, Chairman

Ron Mabra, Vice-ChairmanZoning Ordinance\$5.00Tom MahonSign Ordinance\$3.00Bill BeckwithDevelopment Regulations\$3.00Larry BlanksSubdivision Regulations\$3.00

*(ZBA Members reside in Fayette County and are appointed by the Board of Commissioners)

ZONING BOARD OF APPEALS MEMBERS*

Application requests require a public hearing by the Zoning Board of Appeals (held on the 4th Monday of every month). Application forms must be submitted to the Zoning Administrator <u>by noon</u> on the deadline day. The application deadline is the third Friday of the month prior to the month of the public hearing. The Public hearing is held at the Fayette County Administrative Complex at Stonewall (located at the southwest corner of Hwy 54 and GA 85 in downtown Fayetteville) First Floor in the Public Meeting Room (near the fountain)and begins at 7:00 p.m.

Note: Applications must be filed by the subject property owners or by the authorized agent of the property owners.

APPLICATION FILING FEES

Application Filing Fee: \$175.00 (plus \$25 for each additional variance requested)

Sign Deposit Fee: **\$20.00** per sign A public hearing notification sign is required for each road frontage. The sign deposit of \$20.00 per sign shall be requisitioned for reimbursement to the applicant upon their returning the sign frame(s) to the Zoning Department within five (5) working days following the public hearing.

The application filing fee and sign deposit may be combined on one (1) check made payable to Fayette County. Application filing fees may be refunded ONLY when an application request is withdrawn by applicant PRIOR TO placement of legal advertisement for said public hearing request).

HEARING SCHEDULE FOR 2004 ZONING BOARD OF APPEALS APPLICATIONS

(Dates are subject to change with notice. If a hearing falls on a holiday, a new hearing date will be announced)

<u>APPLICATION DEADLINE</u> (3rd Friday by noon)

HEARING DATE (4th Monday)

(No extensions of deadline are permitted)

submit by . . . November 21, 2003 to be heard by December 15, 2003

December 19, 2003 January 26, 2004

January 16, 2004 February 23, 2004

February 20, 2004 March 22, 2004

March 19, 2004 April 26, 2004

April 16, 2004 May 24, 2004

May 21, 2004 June 28, 2004

June 18, 2004 July 26, 2004

July 16, 2004 August 23, 2004

August 20, 2004 September 27, 2004

September 17, 2004 October 25, 2004

October 15, 2004 November 22, 2004

November 19, 2004 December 27, 2004

December 17, 2004 January 24, 2005

FA	YETTE COUNTY	RESIDENTIA	L ZONING DIST	RICTS
ZONING DISTRICT	ZONING SETBACKS	MINIMUM LOT SIZE	MINIMUM HOUSE SIZE	LOT WIDTH AT BUILDING LINE
A-R Agricultural- Residential/ Single-Family	F-100' Arterial F-100' Collector F- 75' Minor S- 50' R- 75'	5 Acres	1,200	250'
EST Estate Residential District/Single- Family	F-100' Arterial F-100' Collector F- 75' Minor S- 50' R- 75'	5 Acres	4,000	200'
R-85 Single-Family Residential	F-100' Arterial F- 75' Collector F- 50' Minor S- 25' R- 50'	3 Acres	3,000	125'
R-80 Single-Family Residential	F- 75' Arterial F- 75' Collector F- 50' Minor S- 30' R- 50'	3 Acres	2,500	175'
R-78 Single-Family Residential	F-100' Arterial F- 75' Collector F- 50' Minor S- 25' R- 50'	2 Acres	3,000	125'
R-75 Single-Family Residential	F-100' Arterial F- 75' Collector F- 50' Minor S- 25' R- 50'	2 Acres	2,500	125'
R-72 Single-Family Residential	F- 75' Arterial F- 75' Collector F- 50' Minor S- 20' R- 50'	2 Acres	2,100	175' Arterial 175' Collector 150' Minor
R-70 Single-Family Residential	F- 75' Arterial F- 75' Collector F- 50' Minor S- 25' R- 50'	2 Acres	1,500	175' Arterial 175' Collector 150' Minor
R-55 Single-Family Residential	F-100' Arterial F- 75' Collector F- 50' Minor S- 25' R- 50'	1 Acre* 1.5 Acres**	2,500	150'
R-50 Single-Family Residential	F-100' Arterial F- 75' Collector F- 50' Minor S- 20' R- 30'	1 Acre* 1.5 Acres**	2,100	150' Arterial 150' Collector 125' Minor

R-45 Single-Family Residential	F- 60' Major F- 40' Minor S- 20' R- 40'	1 Acre* 1.5 Acres**	1,800	125'
R-40 Single-Family Residential	F- 60' Arterial F- 60' Collector F- 40' Local S- 15' R- 30'	1 Acre* 1.5 Acres**	1,500	150' Arterial 150' Collector 125' Minor
R-20 Single-Family Residential	F- 60' Arterial F- 60' Collector F- 40' Minor S- 15' R- 30'	1 Acre* 1.5 Acres**	1,200	150' Arterial 150' Collector 125' Minor
DR-15 One and Two Family Residential	F- 50' Arterial F- 45' Collector F- 40' Minor S- 10' R- 30'	1 Acre* 1.5 Acres**	1,200 Single-Family 1,800 Two-Family	125' Arterial 125' Collector 100' Minor
R-M-F Multi-Family Residential	Peripheral F-150' State-number route F-100' Arterial F- 80' Collector F- 60' Minor S- 40' R- 40' Minimum 50' building separation	5 Acres Minimum Site Maximum Density 5 Dwelling Units/ Acre 160 Maximum Units	600 Square Feet for One Bedroom 850 Square Feet for Two Bedrooms 1,200 Square Feet for Three Bedrooms	N/A But Minimum 50' Immediate Frontage On Arterial 40% Maximum Lot Coverage
M-H-P Manufactured Home Park	F- 15' S- 4' R- 4'	10 Acres Total Site 6,000 Square Feet Per Lot		60' Per Lot
P-U-D Planned Unit Development	F-Varies S-15' R-30'	100 Contiguous Acres Maximum 4 dwelling units/acre attached Maximum 1 dwelling unit/acre unattached		

^{*} Where a central water distribution system and a private septic system are provided. (County water/septic)

Minimum road frontage: 100' unless on a cul-de-sac 50' per lot for a total of four (4) lots

Arterial A street designated to carry traffic within and through the county. (Major thoroughfare)

Collector A street designated to collect traffic from local or other collector streets. (Major thoroughfare)

Minor A street designated to carry primarily local or residential traffic. (Minor thoroughfare)

^{**} Where public water system is not available. (Well/septic)

^{***} Where a central sanitary sewage and central water distribution systems are provided. (County water/sewage system)

FAYETTE COUNTY NONRESIDENTIAL ZONING DISTRICTS				
ZONING DISTRICT	ZONING SETBACKS	MINIMUM LOT SIZE	LOT WIDTH AT BUILDING LINE	BUFFER
C-C Community Commercial	F- 75' Arterial F- 70' Collector F- 65' Minor S- 15' R- 15'	1 Acre* 0.5 Acres***	125'	50'
C-H Highway Commercial	F- 75' Arterial F- 70' Collector F- 65' Minor S- 15' R- 15'	1 Acre* 0.5 Acres***	125'	50'
L-C Limited Commercial	F- 75' Arterial F- 70' Collector F- 55' Minor S- 15' R- 15'	1 Acre* 1.5 Acres**	125'	50'
M-1 Light Industrial	F-100' Arterial F- 80' Collector F- 65' Minor S- 25' R- 25'	1 Acre* 0.5 Acres***	125'	75'
M-2 Manufacturing and Heavy Industrial	F-100' Arterial F- 80' Collector F- 65' Minor S- 25' R- 25'	2 Acres	125'	75'
O-I Office- Institutional	F- 75' Arterial F- 70' Collector F- 55' Minor S- 15' R- 15'	1 Acre* 0.5 Acres***	125'	30'

Buffer: When the rear or side yard abuts a residential or A-R zoning district, a buffer adjacent to the lot line shall be provided in addition to the required setback. The buffer is measured from the property line and the setback is measured from the buffer.

Updated 05/27/99

CHECKLIST OF ITEMS REQUIRED TO BE SUBMITTED FOR ZBA REQUESTS

(All applications/documentation must be complete at the time of application submittal or the application will not be accepted) Application form and all required attachments, completed, signed, and notarized (if ___ A. applicable). Copy of latest recorded Warranty Deed, including legal description of the boundaries of the ____ B. subject property, including total acreage. ___ C. Fifteen (15) copies of the Plat of property, drawn to scale with accurate dimensions, with the following indicated: ____ 1. Location and size of existing structures (principal and accessory) and improvements on the parcel, including type (residential, non-residential), floor area, building height, and accessory uses. Structures to be removed must be indicated and labeled as such unless demolition or removal will occur prior to applying for a building permit. Minimum setbacks from all property lines of subject property required in the zoning ____ 2. district. _____ 3. Location and dimensions of exits/entrances to the subject property. ____ 4. Location of all existing and proposed easements and streets on or adjacent to the subject property, indicating width of right-of-way, type and width of existing and proposed easements and centerline of streets. ____ 5. Location of well or water lines. _____ 6. Existing septic tank and drainfield location, and replacement area. _____ 7. Approximate location and elevation of the 100-year flood plain (if applicable). _____ 8. On-site stormwater facilities to include detention or retention facilities. _____ 9. Parking locations, approximate number of parking spaces, area for parking bay and aisle dimensions. ____ 10. Landscaped areas and buffers or tree save areas, to include width, general extent and type of materials. ___ D. Application filing fee.

APPLICATION TO THE ZONING BOARD OF APPEALS


PROPERTY OWNERS:	
MAILING ADDRESS:	
PHONE:	FAX:
AGENT FOR OWNERS:	
	FAX:
PROPERTY LOCATION: LAND LO	ΓPARCEL
TOTAL NUMBER OF ACRES OF SUI	BJECT PROPERTY:
ZONING DISTRICT:	
ZONING OF SURROUNDING PROPE	CRTIES:
	RTY:
	ERTY:
(THIS AREA TO BE COMPLETED BY S	STAFF): PETITION NUMBER:
[] Application Insufficient due to lack o	f:
by Staff:	Date:
[] Application and all required supporting	ng documentation is Sufficient and Complete
by Staff:	Date:
DATE OF ZONING BOARD OF APPE	ALS HEARING:
Received from	a check in the amount of \$
	for deposit on frame for public hearing sign(s).
Date Paid:	

PROPERTY OWNER CONSENT AND AGENT AUTHORIZATION FORM

(Applications require authorization by ALL property owners of subject property).

Name(s) of All Property Owners of Record found on the latest recorded Warranty Deed for the subject property:

	Please I	Print Names
Property	Tax Identification Number(s) of Subject Prop	erty:
		property. Subject property is located in Land Lot(s)
		licable to more than one land district) Land Lot(s)
		f a total of acres (legal description corresponding
to most re	ecent recorded plat for the subject property is attack	hed herewith).
(I) (We) l Agent, th	hereby delegate authority toey have the authority to agree to any and all condit	to act as (my) (our) Agent in this request. As tions of approval which may be imposed by the Board.
that this a may not l denial, re	application, attachments and fees become part of the be refundable. (I) (We) understand that any known	f (my) (our) knowledge and belief. Further, (I) (We) understand the official records of the Fayette County Zoning Department and wingly false information given herein by me/us will result in the ication or permit. (I) (We) further acknowledge that additional process this application.
	Signature of Property Owner 1	Signature of Notary Public
	Address	Date
	Signature of Property Owner 2	Signature of Notary Public
	Address	Date
	Signature of Property Owner 3	Signature of Notary Public
	Address	Date
	Signature of Authorized Agent	Signature of Notary Public
	Address	Date



[] So Request for Continuance of Nonconformance: The Board may allow a nonconformance to be re-established after discontinuance for six (6) consecutive months where it is deemed by the Board that: (1) the design, construction, and character of the land, building, or structure is not suitable for uses permitted in the zoning district in which the nonconformance is situated; (2) undue hardship to the property owner would result in not allowing the continuance of a nonconformance; (3) adjacent property would not be unduly damaged by such continuance; and (4) the use is to be identical to the prior nonconformance.

Where an application to the Board is initiated due to an existing violation of the Zoning Ordinance and said application is <u>DENIED</u> by the Zoning Board of Appeals, the violation shall be required to be corrected within TEN (10) days of such denial or as specified by the Board if a greater time period is necessary. The maximum extension of the time can not exceed 30 days.

VARIANCE INFORMATION

Complete the chart below with the information pertaining to each request. If there are more than three (3) variances requested, please provide the information on a separate sheet of paper.

Ordinance/Section	Requirement	Proposed	Variance Amount

VARIANCE SUMMARY

Provide a detailed and specific summary of each request. separate sheet of paper.	If additional space is needed, please attach a

JUSTIFICATION OF REQUEST

The Fayette County Zoning Ordinance, Section 9-2.B. states that in order to grant a variance, the Zoning Board of Appeals shall and must find that all six (6) conditions below exist. Please read each standard below and then addess each standard with a detailed response. Attach additional information/documentation as necessary.

	e are extraordinary and exceptional conditions pertaining to the particular piece of
prope	erty in question because of its size, shape or topography.
	application of these regulations to this particular piece of property would create cal difficulty or unnecessary hardship.
Such	conditions are peculiar to the particular piece of property involved.

purposes a	granted, would not cause substantial detriment to the public good or impair to and intent of these regulations; provided, however, no variance may be granted fund, building, or structure that is prohibited herein.
A literal in	nterpretation of this Ordinance would deprive the applicant of any rights that other
	ne zoning district are allowed.
may be ne and to pro wherever of these re was grante after givin In exercis neighborin	that the Board may impose or require such additional restrictions and standards cessary to protect the health and safety of workers and residents in the communit tect the value and use of property in the general neighborhoods; and provided the Board shall find, in the case of any permit granted pursuant to the provision gulations, that any of the terms, conditions, or restrictions upon which such permediate are not being complied with, said Board shall rescind and revoke such permediate notice to all parties concerned and granting full opportunity for a hearing the above powers, the Board shall not consider any nonconforming useing lands, structures or buildings in the same zoning district, and no permitted uttructures, or buildings in other zoning districts as grounds for issuance of variance to the same and the same control of the s
after givin In exercis neighbori	ng due notice to all parties concerned and granting full opportunity for a hearing the above powers, the Board shall not consider any nonconforming use

HEARING SCHEDULE FOR 2004 - ZONING BOARD OF APPEALS APPLICATIONS

(Dates are subject to change with notice. If a hearing falls on a holiday, a new hearing date will be announced)

APPLICATION DEADLINE (3rd Friday by noon) (No extensions of deadline are permitted)		HEARING DATE (4th Monday)	
submit by	December 19, 2003	to be heard by	January 26, 2004
	January 16, 2004		February 23, 2004
	February 20, 2004		March 22, 2004
	March 19, 2004		April 26, 2004
	April 16, 2004		May 24, 2004
	May 21, 2004		June 28, 2004
	June 18, 2004		July 26, 2004
	July 16, 2004		August 23, 2004
	August 20, 2004		September 27, 2004
	September 17, 2004		October 25, 2004
	October 15, 2004		November 22, 2004
	November 19, 2004		December 27, 2004
	December 17, 2004		January 26, 2005